

Layout Diversion and Feeder Pipeline



| | |
|-----------------------------------|-------------------------------|
| Diversion Type | Drop Inlet |
| Pipeline Type | Asbestos-cement pressure pipe |
| Crest Length..... | 10 feet |
| Crest Elevation..... | 7,902 feet |
| Capacity | 20 cfs |
| Length of Feeder Pipeline..... | 4,323 feet |
| Diameter of Feeder Pipeline | 18 inch to 15 inch |
| Construction Costs | \$675,055 |
| Construction Period | 1970 - 1975 |
| Water Course | Layout Creek |
| Initial Diversions..... | 1/31/75 |