

Rhodes Diversion and Feeder Pipeline



Diversion Type	Drop Inlet
Crest Length	20 feet
Crest Elevation	7,891 feet
Capacity	30 cfs
Length of Feeder Pipeline	706 feet
Diameter of Feeder Pipeline	2.5 feet
Construction Costs (includes Win Diversion)	\$1,490,628
Construction Period	9/5/86 - 7/15/88
Water Course	Wolf Creek
Initial Diversions	1/14/88