

# Syar Tunnel



Finish Type ..... Cast-in-Place Concrete  
Length ..... 5.7 miles  
Diameter..... 8.5 feet  
Capacity ..... 660 cfs  
Maximum Flow Depth..... Full  
Construction Costs ..... \$67.7 million  
Construction Period ..... 20 Sep 1988 – 20 Feb 1992  
Initial Diversions..... 4 June 1996