

West Fork Pipeline



Type	Reinforced Concrete Cylinder Pressure Pipe
Length	4.2 miles
Diameter.....	6.5 feet
Capacity	325 cfs
Maximum Flow Depth.....	Full
Construction Costs (includes Vat Diversion Dam)	\$13,908,588
Construction Period	4/27/79 - 6/1/85
Initial Diversions.....	12/28/87