

Win Diversion and Feeder Pipeline



Diversion Type	Drop Inlet
Crest Length.....	15.1 feet
Crest Elevation.....	7,903 feet
Capacity	5 cfs
Length of Feeder Pipeline.....	3,380 feet
Diameter of Feeder Pipeline	1.5 feet
Construction Costs	
(includes Rhodes Diversion).....	\$1,490,628
Construction Period	9/5/86 - 7/15/88
Water Course	Twin Creek
Initial Diversions.....	5/25/88